

City of Wichita, Kansas

Americans with Disabilities Act Transition Plan

Murdock Park

1808 E. Murdock

July 2005



Prepared by

DMCG

Disability Management Consulting Group L.L.C.

2801 Jonquil Place
Columbia, MO 65202

In conjunction with

The Great Plains ADA & IT Center and the City of Wichita Disability Advisory Board

City of Wichita – ADA/504 Transition Plan – Murdock Park - July 2005

Legend: **Blue** font identifies hyperlinked documents – **Red** font indicates recommended changes to structures or policies

Locations	Structural Inconsistencies		Recommended Corrections/Modifications to Ensure Program Access	Criteria – L=low, M=medium, H=high			Supplemental Technical Information			Finalized Actions		
Location	Identified Issue	ADAAG Specifications	Recommended Correction	Priority (overall)	Public Access	Frequency - PWD	Photo #	Conceptual Costs	Support Information	Finalized Correction	Date to be Corrected	Date Completed (Include initial)
2. An accessible path of travel does not lead to the picnic shelter.	An accessible path of travel does not exist leading to the picnic shelter due to a dirt/grass surface.	4.1.2 4.5.1	The program access provisions of Title II , requires all services or programs owned or operated by a Title II entity be accessible in some manner. We consider that shelters, which are open to the general public in city parks, are programs and services offered by the City. Accessible routes must lead to buildings and facilities that are open to the general public. An accessible route must consist of a stable, firm and slip-resistance surface (concrete, asphalt or rubber). Provide at least one accessible path of travel to the shelter, which leads from other pedestrian pathways.	H	M	M	1 2	\$1,000	Accessible Routes Checklist			
3. Restrooms	Braille and raised letter signage does not exist at the entrance doors to the men’s and women’s restrooms.	4.1.3(16) 4.30.4	Signs that identify permanent rooms and spaces are required to be provided in Braille, mounted at 60-inches high measured to the center of the sign located at the latch side of the door. Provide Braille and raised letter signage at the latch side of entrance doors.	M	H	M	3	\$50	Signage Specifications for Permanent Rooms and Spaces			
4. Restrooms	An accessible toilet stall does not exist in the men’s or women’s restrooms due to numerous barriers.	4.23	Inconsistencies include, but are not limited to: narrow stall, narrow stall door opening, lack of grab bars at rear of stall, etc. In new construction, ADAAG requires all public restrooms to be fully accessible. We recommend making these restrooms fully accessible according to ADAAG specifications, unless doing so is technically infeasible.	M	H	M	2 6	\$4,000	Restroom Figures – Building Blocks			

Murdock Park - Conceptual Cost Projections

Total	\$8,050
Year One (Very High)	\$0
Year Three (High)	\$1,000
Year Five (Medium)	\$4,050
Year Ten (Low)	\$3,000